

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>18</u> N. <u>●</u> R. <u>11</u> W. <u>●</u>	E-1 B-1;B-3;C-1;C-3;D-1
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

E-1	C-3	D-1
Fd. 1/2 x 18 re-rod	Fd. & accepted fence post iron	Set DNR Mon. & Cedar Post
16 Oak N08°W 39.62	in center E-W dirt road	5" W. Pine S40°E 12.0
14 Pop S53E 42.32	10" W. Oak S47°E 93.57	10" B. Oak S05°W 41.0
15 Oak N84E 35.31	8" J. Pine S02°W 57.30	S¼ Sec. 32 (19-11) S89°25'W 41.29
SE COR. SEC. 32, T19N, R11W, S89-25W, 39.6	8" J. Pine N08°W 53.80	Ctr. N-S gravel rd. Due W 41±
	Set Cedar Post w/loc. tag	

E-1: Fd. & accepted 1/2 inch re-rod as estab. by <sup>Due N 33'</sup> RLS, James P. Fraus in 1972.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-1 Reestablished N¼ corner, Sec. 6 (18-11) at prorated distance to G.L.O. survey between NE and NW corners of Sec. 6 and on south line of SE¼ of Sec. 31 (19-11).
- B-3 Found ½" pipe as established by R.L.S. Clint Cole on line between section corners to E and W and at prorated distance to G.L.O. survey.
- C-1 Reestablished NE corner of Sec. 6 (18-11) at closing U.S. distance E (1.20 ch.) of standard corner and on line between SW and S¼ of Sec. 32 (19-11).
- C-3 Found fence post iron as recovered by R.L.S. Clint Cole.
- D-1 Reestablished N¼ corner Sec. 5 (18-11) equidistant between NE and NW corners of Sec. 5 and on south line of SE¼ of Sec. 32 (19-11).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1	B-3	C-1
Set DNR Mon. & Cedar Post	½" Pipe & Cedar Post	Set DNR Mon. & Cedar Post
24" R. Pine N25°E 19.9	w/loc. tag	5" Maple S70°E 29.3
10" B. Oak N80°E 36.5	6" J. Pine N88°W 9.77	6" Maple S10°W 17.9
S¼ Sec. 31 (19-11)	14" J. Pine S32°E 12.09	SW Corner Sec. 32 (19-11)
N89°58'30"W 72.9	10" J. Pine N51°E 62.55	N89°58'30"W 79.20
	Ctr. E-W dirt rd. (in Curve)	E-W Random Due S 1.3
	Due N 18'	

SIGNED BY Carl F. Roser 4-28-77 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

PINORA TOWNSHIP  
LAKE COUNTY