

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>18</u> N. <u>●</u> , R. <u>11</u> W. <u>●</u>	D-7; E-6; E-7; E-9
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 5-14-73 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- D-7 Found iron and three F.Jones NBTs in center of N-S road. Old corner of record.
 - E-6 Found iron and one G. Johnson NBT. Old corner of record.
 - E-7 Found iron and one witness form survey of R.H. Hollistier, 1903
 - E-9 Monumented corner of record by G. Blass.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7	E-7	E-9
Fd. Iron & stks. Added DNR buried mon.	Fd. iron. Added DNR buried Mon.	Fd. B. spk, added DNR Mon.
17" B.Oak S35W 58.5'	21" W. Pine N55W 67.7'	8" Maple N57E 63.4
11" J. Pine N37E 66.2'	10" Cherry N75E 40.2	20" B. Oak N28W 63.1
18" B.Oak S77E 65.0	fn cor & loc tag Due E 18'	Power Pole S48E 49.3
Set Ced. post w/loc tag Due E 33'	7" Hemlock S50W 41.3'	Ced post & loc tag N45E 40'
	E-6	
	Fd pipe, added DNR Mon & Ced Post	
	11" W. Oak 2-clmp N05E 33.0	
	11" W. Oak S82W 33.1	
	7" Maple S25W 50.1	


SIGNED BY Carl F. Roser DATE 9-24-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____