

223 2 9 1988

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0179

For corners in
Lake _____

	Located In:		Corner Code #
	18N	11W	
1. Public Land Survey	T	R	H-9
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

REGISTER OF DEEDS
 Recorder M. Adams
 Oct 29 4 40 PM '98
 LAKE COUNTY, MI.
 RECORDED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Robert L. Wetherell, in a field survey on March 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-9 - 1/4 Corner common to Sections 22 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

- | | |
|------------------------------------|---|
| 1838 - J. Hodgson, G.L.O. - | 1917 - G. Johnson, Co. Surveyor |
| #1 - 10" Pine N17°W 15 Links | #5 - 5" Beech S28°E (no distance given) |
| #2 - 8" Maple S13°E 9 Links | #6 - 24" Pine Stump N30°E 20.0' |
| Undated County Survey Records | |
| #3 - 14" Pine Stump N60°E 53 Links | |
| #4 - 24" Pine Stump N27°W 34 Links | |

- 1973 - Carl Roser, LS 12028
 L.C.R.C. - Liber 02, Pg. 162.
 "Found 7/8" x 30" iron by corner of fence post which fits G. Johnson witnesses. Added D.N.R. Monument".
 #7 - 17" W. Oak N50°W 25.7'
 #8 - 23" R. Oak S70°E 10.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 - 1/4 Corner common to Sections 22 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

I found the D.N.R. Aluminum Capped Monument 2.5 feet South of fence intersection (north and east).

Condition of the accessories are as follows: #1 gone, #2 Gone, #3 Gone, #4 Gone, #5 Gone, #6 Gone, #7 Found Stump, #8 Found Stump.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN C. J. W.
 DATE 10-27-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 - 1/4 Corner common to Sections 22 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

I accepted the D.N.R. Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 5" R. Oak N86°W 48.05' (60d spike in S. side)
- 8" R. Oak N35°W 42.98' (60d spike in W. side)
- 6" W. Oak S35°E 57.98' (60d spike in S.W. side)
- 5" Maple N54°E 42.33' (60d spike in N.W. side)

Signed by Robert L. Wetherell
 Surveyor's Michigan License No. 24624

Date 10-29-98

