

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE LIBER 003 PAGE 0228
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in
Lake

(County)	Located In:	Corner Code --#
1. Public Land Survey	T 18 N R 11 W	I-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
 Oct 7 3 46 PM '94
 RECORDED
 LAKE COUNTY, MI.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on April 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1 - (Section corner for Sections 2 and 3, T18N, R11W, on Township Line)

- | | | |
|---|---|---------------------------------------|
| <u>1838 - John Hodgson, D.S. G.L.O.</u> | <u>1917 - George Johnson, County Surveyor</u> | <u>1973 - James Fraus, L.S. 17089</u> |
| #1 - 28" Hemlock S2°E 46 Links | Monument (2" x 4" Angle Iron) | Set a P.K. Nail for Monument at |
| #2 - 11" Cedar S42°W 28 Links | #3 - 6" Cedar S67°30'E 18' | G.L.O. record distance from the |
| S.W. Cor. Sec. 35 - 65 Links West | #4 - 6" Hemlock S6°W 20.8' | corner common to Sec's. 2, 3, 10 |
| | | and 11. L.C.R.C. - Liber 02, |
| | | Page 156. |

(SEE OVER FOR CONTINUATION OF "A" - DESCRIPTION OF ORIGINAL MONUMENT)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 - (Section corner for Sections 2 and 3, T18N, R11W, on Township Line)

I found the 2" x 4" Angle Iron by George Johnson (1917) 4 feet below the surface of blacktop road, in an old roadbed. The Angle iron is 6.5 feet East of the Railroad spike used by Clinton E. Cole and 22.4 feet South of corner position by James Fraus. I accepted the 2" Angle Iron as the true location for the corner. Condition of witnesses are: #1 - Gone, #2 - Gone, #3 - Gone, #4 - Gone, #5 - Found in good condition, #6 - Found in good condition, #7 Found in good condition, #8 - Found in good condition, #9 - Found in good condition, #10 - found in good condition, #11 Found in good condition.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 - (Section corner for Sections 2 and 3, T18N, R11W, on Township Line)

I set a 3/4" x 24" re-bar with Lake County Brass Cap directly over the 2" x 4" Angle Iron, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 8" Cedar N85°W 34.15' (60d spike in North side of tree) (#8)
- 9" Elm N28°E 63.79' (60d spike in Northwest side of tree) (#9)
- 6" Cedar S79°E 42.28' (60d spike in North side of tree) (#10)
- 24" W. Pine S31°E 42.91' (60d spike in Northeast side of tree) (#11)

Signed by Robert L. Wetherell Date October 4, 1994
 24624



Surveyor's Michigan License No. _____
 PATIFIED BY THE LAKE CO. PEER REVIEW GROUP
 IN ACCORDANCE WITH P.A. 345
 CHAIRMAN W. L. W.
 DATE 10-4-94

CONTINUATION OF "A" - DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION

I-1 - (Section corner for Sections 2 and 3, T18N, R11W, on Township Line)

1980 - Clinton E. Cole, L.S. 17615

Used Railroad spike in approximate center of Blacktop road.

#5 - 8" Cedar N84°W 27.80'

#6 - 22" W. Pine S38°E 47.44'

#7 - 8" Cedar N64°E 42.38'

1993 - Robert L. Wetherell, LS 24624

(2" x 4' Angle Iron) Raised to surface with 1/2" Iron.

8 - 8" Cedar N85°W 34.15'

9 - 9" Elm N28°E 63.79'

#10 - 6" Cedar S79°E 42.28'

#11 - 24" White Pine S31°E 42.91'

L.C.R.C. Liber 003, Pg. 167

OLIVER &
REMONUMENTATION

NOV 15 1994

COMMISSION