

DEC 8 9 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 004 PAGE 0178

For corners in
Lake

(County)	Located In:		Corner Code #
	18N	11W	I-9
1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S	T	_____
	S	T	_____
3. Miscellaneous Property in Sec.	S	T	_____
	S	T	_____

REGISTERED
LAKE COUNTY, MI.

OCT 29 4 40 PM '98

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on March 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-9 - Section corner common to Sections 22, 23, 26 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

1838 - J. Hodgson, G.L.O.
14" B. Oak For Corner

1917 - G. Johnson, Co. Sur.
1-1/2" Round Iron 16" long
#1 - 16" Pine Stump N53°E 11.5'
#2 - 12" Pine Stump N74°W 11.5'

1973 - C. Roser, LS 12028
L.C.R.C. Liber 02, Pg. 162
"Found 1-5/8" Iron by rotted
off fence corner post".
Added D.N.R. Monument
#3 - 12" Maple N21°W 25.9'
#4 - 16" Maple N36°E 42.3'
#5 - 5" Tw. Beech S42°W 22.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 - Section corner common to Sections 22, 23, 26 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

I found the D.N.R. Aluminum Capped Monument 0.4 feet South of corner fence post.

Condition of the accessories are as follows: #1 Found rotted remains, #2 Found rotted stump, #3 Found dead, #4 Found in good condition, #5 Found stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 - Section corner common to Sections 22, 23, 26 & 27, T18N, R11W, Pinora Twp., Lake Co., Mi.

I accepted the D.N.R. Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 7" R. Oak N45°E 7.24' (60d spike in S.E. side) found blazes on face of tree.
- 6" R. Oak S88°W 24.83' (60d spike in S. side)
- 7" R. Oak S11°E 29.32' (60d spike in E. side) found blazes on face of tree
- 5" Beech S78°E 30.53' (60d spike in N. side)

Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date 10-29-98

HATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R. J. W.
DATE 10-27-98

