

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0231

COMMISSION

For corners in

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 18 N R 11 W	J-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTERED
LAKE COUNTY, MI.
OCT 7 3 46 PM '94
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Wetherell, in a field survey on April 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 - (North 1/4 corner of Section 2, T18N, R11W, Lake Co., Mi.)

Not being established by G.L.O., in 1980 I set a 1/2" iron rod equal distance between the Northeast and Northwest corners of Section 2, and on the township line. Distances each way being 2,613.99 feet.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 - (North 1/4 corner of Section 2, T18N, R11W, Lake Co., Mi.)

In 1993, I discovered that I had used the wrong corner for the Northwest corner of Section 2, in my 1980 survey. Therefore, the position for the North 1/4 corner I had established at that time was incorrect. I re-measured (1994) the distance between the correct Northwest Section corner and the Northeast Section corner (5221.47') and re-set the 1/4 corner equal distance and on line between the respective Section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 - (North 1/4 corner of Section 2, T18N, R11W, Lake Co., Mi.)

I set 3/4" x 24" re-bar with Lake County Brass Cap. This position not established by G.L.O. This monument is accepted as the best available evidenced of the position of the original corner.

- 5" G. Birch S80°E 11.95' (60d spike in North side)
- 5" Maple N76°W 5.88' (60d spike in South side)
- 5" Maple S19°E 43.22' (60d spike in West side)
- 6" Maple S39°W 48.45' (60d spike in West side)

Signed by Robert L. Wetherell Date October 4, 1994
Surveyor's Michigan License No. 24624

