

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0260

For corners in COMMISSION

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 11W	K-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED  
LAKE COUNTY, MI.  
OCT 27 3 20 PM '94  
REGISTER OF DEEDS  
*Shirley N. [unclear]*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 - Corner common to Sections 35 & 36 on Township Line, T18N, R11W, Pinora Twp., Lake Co., Mi.

1837 - John Hodgson, D.S., G.L.O.  
 #1 - 16" Hemlock N50°E 48 Links  
 #2 - 18" Hemlock N29°W 17 Links

1891 - A.O. Temple, Surveyor  
 Broke Section 36, (T18N, R11W)  
 W. 1/4 Cor. Sec. 36 - North 39.90 Chains (2633.4')  
 S. 1/4 Cor. Sec. 36 - East 39.78 Chains (2625.48')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 - Corner common to Sections 35 & 36 on Township Line, T18N, R11W, Pinora Twp., Lake Co., Mi.

I was unable to recover any monument for this corner. I re-established the corner by setting it record distance (G.L.O.) 44.88 feet (68 Links) West on the Township Line of the found closing corner of Sections 1 and 2 of T17N, R11W. From this position I measured 2629.5 feet to the 1/4 corner North and 2623 feet more or less East to a fence line running North. Which is consistent with Temple's distance in 1891. Corner falls in the center of East and west blacktop road and 41 feet more or less West of a North and South blacktop road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 - Corner common to Sections 35 & 36 on Township Line, T18N, R11W, Pinora Twp., Lake Co., Mi.

I set a 3/4" x 24" re-bar with Lake County Brass Cap in a monument box and is accepted as a careful and faithful re-establishment of the position of the original corner.

Power Pole S66°E 96.69' (Found nail with cap)  
 Power Pole N80°E 96.19' (Found nail with cap)  
 12" W. Pine N80°W 327.17' (60d spike in South side of tree)  
 3/4" x 24" Re-bar with brass cap East 44.88'

Signed by Robert L. Wetherell Date 10-26-94

Surveyor's Michigan License No. 24624 RATIFIED BY THE LAKE CO. PEER REVIEW GROUP

IN ACCORDANCE WITH P.A. 345  
 CHAIRMAN [Signature]  
 DATE 10-25-94

