

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 18 <sup>N.</sup> <input checked="" type="radio"/> R. 12 <sup>W.</sup> <input checked="" type="radio"/>	K-3; K-4; L-3; L-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. = Description of original monument and accessories and of subsequent restoration.~~

C. (continued)

L-5			
Set DNR mon. & cedar post			
5" R. Oak	N60°E	10.8	
4" Maple	S80°E	7.2	
7" W. Oak	S75°W	5.6	
E-W random	Due N	7.8	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-3 Reestablished corner per standard B.L.M. instructions, double proportionate to U.S.
- K-4 Reestablished corner per standard B.L.M. instructions, single proportionate to U.S.
- L-3 Reestablished corner per standard B.L.M. instructions.
- L-5 Reestablished corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3	K-4	L-3
Set DNR mon. & cedar post	Set DNR mon. & cedar post	Set DNR mon. & cedar post
9" W. Oak N32°W 12.6	4" Maple N73°E 20.1	5" Oak N35°E 12.8
16" W. Pine N70°E 9.9	10" W. Oak S70°E 13.4	5" Oak S10°W 6.9
14" W. Pine S10°W 36.0	11" B. Oak S15°E 8.9	5" Oak S65°W 6.9

SIGNED BY Carl F. Roser 9-4-75 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ CHERRY VALLEY TOWNSHIP  
LAKE COUNTY