

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 18 ^{N.} R. 12 ^{W.}	L-7; M-7
2. PROPERTY CONTROLLING IN SECTION 13	T. 18 ^{N.} R. 12 ^{W.}	8; 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ ^{N.} R. _____ ^{E.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 29, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~
 C. (continued)

15
 Set 1"x30" Pipe & cedar post
 w/loc. tag
 12" R. Oak N65°W 19.9
 5" Maple S40°W 20.2

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 Reestablished corner per standard B.L.M. instructions.
- M-7 Found iron from two F. Jones witnesses, dated 1935.
- 8 Established corner per standard B.L.M. instructions. One-strand fence corner (tree) is 132' South & 32' West.
- 15 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7	M-7	8
Buried DNR monument	Found iron & added DNR mon. and cedar post	Set 1"x3' Pipe & cedar post w/loc. tag
7" R. Pine N70°E 88.7	6" W. Oak N80°E 97.0	22" B. Oak N65°E 9.3
8" W. Oak S50°E 39.5	NW leg steel tower #3972	7" R. Oak N60°W 26.3
Set cedar post w/loc. tag	S40°E 52.6	
Due N 33		
Center E-W dirt road		
Due N 10		

SIGNED BY Carl F. Roser 9-4-75 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

CHERRY VALLEY TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____