

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. 18 N. 12 E.	18 N. 12 E.	A-13; C-12
2. PROPERTY CONTROLLING IN SECTION 31, T. 18 N. 12 E.	18 N. 12 E.	12
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ E.	N. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Jan. 16, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-13 Fd. 3/8" Iron in Mon. Box that fits RLS, C. Cole Wits., 1975 and Blass survey of Sec. 31 dated 1954.
- C-12 Fd. & used 3/4 " bolt as previously fd. & used by RLS's, G.Gray & C.Cole. This corner is suspect as we recovered a pointed stake bottom, in muck, from G.West Wit., dated 1921, 20" Elm (dead stub), N03 1/2°W, 14'; said pointed stk. bottom being 7'E & 2.5N of bolt.
- 12 Established 1/8 corner per std. BLM instructions. Corner falls at old sq'd 3"X3" Ced.post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13	C-12	12
Fd. & accepted 3/8"X3/8"iron in Mon. Box 3' S of U.S. 10 Ctr. line.	Fd. 3/4"X22" bolt; added in exact same position a DNR Mon. & Ced. Post.	Set 5/8"X40" iron rod w/RLS Cap & Ced.Post w/Loc. Tag
Power Pole N13°W 124.75	5" W.Pine N85°E 72.5	9" Hemlock S05°E 57.7'
32" B.Oak N15°E 133.89	15" W.Pine S70°E 51.3	10" Cedar S55°W 72.7'
11" W. Oak S25°E 85.16	Ctr. Sanborn Creek	Ctr. Power line S'ly Due W 30'
	Ctr. Sanborn Creek	Ctr. E-W Power line Due N 52'
	Due N 94'+	
	Due W 96'+	


SIGNED BY Carl F. Roser 1-18-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHERRY VALLEY TOWNSHIP
LAKE COUNTY