

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 18 N. R. 12 W.	G-2
3. Misc. Prop. in Sec. 3	T. 18 N. R. 12 W.	*1151.5' S. of #3 (sec. 3) & 164.5'-N of G-2
PROPERTY CONTROLLED BY PROPERTY IN SECTION 3	T. 18 N. R. 12 W.	**987.0'S of #3 (Sec.3)
3. MISCELLANEOUS PROPERTY IN SECTION 3	T. 18 N. R. 12 W.	* 329.0'-N of G-2
4. LOT NO. _____, RECORDED PLAT _____	T. 18 N. R. 12 W.	***822.5'S. of #3 (Sec.3) & 493.5-N of G-2
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 10, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on May 10, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

 Set 5/8"X40" rod w/RLS cap &
 Ced. Post w/loc. tag
 16" Ced.stp. lying E'ly
 N10°W 8.4
 8" Ced. *Stub* N30°E 23.4
 N-S Rand Due E 0.2

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-2 Restored corner per standard BLM instructions which fell in area of old N-S wire on ground.
- * Set NW Cor., S 1/4, S 1/2, SW 1/4, NW 1/4, Sec. 3, per standard BLM instructions.
- ** Set SW Cor., S 1/2, N 1/2, S 1/2 SW 1/4, NW 1/4, Sec. 3, per standard BLM instructions.
- *** Set NW Cor., S 1/2, N 1/2, S 1/2, SW 1/4, NW 1/4, Sec. 3, per standard BLM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2		*	**Rod
Set DNR Mon. & Pointed Ced. Post	Set 5/8"X40" rod w/RLS cap &	Set 5/8"X40" w/RLS cap &	
11" Ced.stp. Due N 20.3	Ced.post w/loc. tag	Ced.Post w/loc.tag	
5" Cedar N85°E 8.7	5" Cedar N70°W 6.1	9" Cedar S30°E 14.3	
6" Cedar S35°E 6.8	7" Cedar N80°E 23.0	6" Cedar S53°W 16.6	
	N-S Rand Due E 0.2	N-S Rand Due E 0.2	

SIGNED BY Carl F. Roser DATE 5-15-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

CHERRY VALLEY TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____