

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 18 N. R. 12 W.	A-11; B-10; B-11; C-9
2. PROPERTY CONTROLLING IN SECTION	29 T. 18 N. R. 12 W.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 13, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~xxx Description of original monument and accessories and corner recordation:~~

C. (continued) e-9 15

Fd. 1" pipe & added Ced. Post w/loc. tag	Set 5/8X40" rod w/RLS cap in ctr E-W rd.
18" W.Pine S05°E 78.9	9" B.Oak S03°E 65.2
10" W.Pine S45°W 59.4	7" B.Oak S55°W 59.4
11" W.Pine S40°E 18.4	Set Ced. Post w/loc. tag
	Due N 33'

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-11 Found "T" Ir. that fits Wit. by R.L.S., Matt McClung. Blass notes, 1954, call for "T" Ir. Fd. nail, 10' south, that could have fit 1954 Blass Wits.?
 - B-10 Fd. 3/4" iron as estab. by RLS, Matt McClung, May 1971.
 - B-11 Fd. 3/4" Ir. rod with RLS Cap (Matt McClung) inside 1 1/2" pipe.
 - C-9 Fd. 1" pipe that fits 1929 Wit. by G.H.Johnson. Cor. also subsequently used & witnessed by RLS's, Matt McClung and Robt. Griffin.
 - 15 Estab. 1/8 Corner per std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>A-11</u> Fd. "T" iron & raised w/1/2"X7" pipe	<u>B-10</u> Fd. 3/4 iron rod in ctr. E-W Rd.	<u>B-11</u> Fd. 3/4 iron rod w/RLS cap inside 1 1/2" pipe & added Ced. Post w/loc. tag
15" B.Oak S45°E 77.79	5" B.Oak N10°E 53.2	26 W.Pine N40°E 93.5
12" W.Oak S40°W 81:89	5" W.Oak S50°E 42.8	13" Maple S25°E 45.7
Set Ced. Post w/loc. tag S45°E 47'	8" B.Oak S53°W 37.9	12" Ironwood S30°W 31.1
Ctr. E-W sand rd. Due S. 9'+	Set ced. Post w/loc. tag Due N 33'	


SIGNED BY Carl F. Roser DATE 5-15-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHERRY VALLEY TOWNSHIP
LAKE COUNTY