

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>18</u> ^{N.} W. , R. <u>12</u> ^{W.} N.	<u>A-9;A-10</u>
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>18</u> ^{N.} W. , R. <u>12</u> ^{W.} N.	<u>10; 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} W. , R. _____ ^{E.} S.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 2, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~xxx Description of original monument and accessories and/or subsequent restoration xxx~~
 C. (continued) 15

Set 5/8X40" rod w/RLS Cap
 & Ced. Post w/loc. tag
 8" B. Oak N40°W 45.1
 11" B.Oak N23°E 35.7
 Ctr. E-W Sand Rd.
Due S 17'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-9 Fd. 1/2"X 1/2" Sq. iron (buried) in approx. ctr. of N-S B.Top road. Fits Wits. by R.L.S.'s, Robt. Griffin and Matt McClung. Corner restored by Griffin from Blass Wits.
- A-10 Fd. 1/2 rod as estab. by R.L.S., Matt McClung, May 1971; with R.L.S., Gray's cap. Corner falls in "T" road intersection.
- 10 Fd. 1" pipe for 1/8 Cor. Fits mid-way & on line between 1/4 Cor. N. & Sec. Cor. S.
- 15 Estab. 1/8 Cor. on line & at pro-rated dist. to G.L.O. between Sec. Cor. W. & 1/4 Cor. E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9	A-10	10
Fd. 1/2" X1/2" Sq. Ir., (buried)	Fd. 1/2" X16 rod w/RLS cap over buried iron	Fd. 1" pipe; raised w/3/8X10" spk.
22" W.Pine S87°W 68.03	20" B.Oak N28°W 66.34	7" B.Oak N60°E 45.8
13" B. Oak N25°W 57.47	7" W.Oak N55°E 70.05	6" R.Pine S70°E 47.7
20" B.Oak N40°E 51.23	Set Ced.Post w/loc. tag	Fd. 3/4" pipe Due W 33.0
14" W.Oak Due E 37.86	Due W 33'	Set Ced.Post w/loc.tag
Set Ced.post w/loc.tag		Due E 33'
Due E 33'		


SIGNED BY Carl F. Roser 5-15-78 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHERRY VALLEY TOWNSHIP
LAKE COUNTY