

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION 27	T. 18 N. S., R. 12 E. W.	6; 9
3. MISCELLANEOUS PROPERTY IN SECTION 27	T. 18 N. S., R. 12 E. W.	*330.1'-S of #2
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER _____

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 18, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on December 18, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 6 Established center of NE 1/4 of Sec. 27 per Std. B.L.M. instructions. Iron by Lake State Sur. & Eng. (1972) as noted in Wits.
 - 9 Established E 1/8 Cor. on E-W 1/4 line, Sec. 27, per Std. B.L.M. instructions.
 - * Estab. NE Cor. of S 3/4 - NW 1/4 - NE 1/4 of Sec. 27 per Std. B.L.M. instructions. Iron by Lake State Sur. & Eng. (1972) as noted in Wits.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6	9	*
Drove 5/8"X40" re-rod w/RLS cap & Set Ced. Post w/Loc. Tag.	Drove 5/8"X40" re-rod w/RLS cap.	Drove 5/8"X40" re-rod w/RLS Cap & Set Cedar Post w/Loc. Tag.
8" Blk. Oak N20°W 19.0'	12" W.Pine N55°W 45.9'	5" W.Pine N40°E 47.9'
14" W.Pine N75°E 34.3'	4" B. Oak N70°E 29.0'	4" R.Pine S80°E 59.7'
Fd. iron N88°46'W 11.41'	Set Ced.Post w/Loc. Tag	Fd. Iron N85°W 13.95'
	Due N 33'	
	Ctr. E-W dirt rd.	
	Due S 10'	

SIGNED BY Carl F. Roser 5-23-79 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHERRY VALLEY TOWNSHIP
LAKE COUNTY