

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. 18 N. 12 R. W.	H-8; H-9
2. PROPERTY CONTROLLING IN SECTION.....	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 31, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 H-8 Established Ctr. of Sec. 22 at intersection of one-quarter lines. The iron that Geo. Johnson describes in his "minutes of survey", 1916, was found sticking in top of pine stump-- "had been pulled".

H-9 Fd. well point as called for by Geo. Johnson survey of Sec. 22, Dec. 1916. Johnson's "minutes of survey" indicate he re-established the S 1/4 Cor. of Sec. 22 by single proportion between the SE & SW Cor.'s of Sec. 22; we found well point to fit this position very close. Fd. 7/8"X24" bolt w/nut, lying on ground, from three Wetherell Wits. (1972); which is N87°W, 29.34; from fd. Well Point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-8	H 9
Re-set Johnson's 1 1/2"X38"X32" Wagon Tire Iron at Inter. of 1/4 lines and set Ced. Post w/Loc. Tag.	Fd. well point; added DNR Mon & Ced. Post.
6" B. Oak N25°W 9.6'	9" Maple N45°E 20.6'
5" W.Oak S55°E 27.1'	16" Basswood S60°E 31.9'
8" R. Maple S75°W 14.4'	10" Maple S10°W 11.0'
Fn. Cor. remains N, S & E	Old R.R. grade Due N 342'
Due N 7'	

Accepted Fd. Well Point to Secs 22 & 27.


SIGNED BY Carl F. Roser DATE 5-23-79

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



CHERRY VALLEY TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____