

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
LAKE

(County)

Located In:

Corner Code 11

1. Public Land Survey	T	<u>18N</u>	R	<u>12W</u>	
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	<u>31</u>	T		<u>15</u>
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, C.T. KIISKILA, in a field survey on JAN. 19, 19 95  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
15

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S. LINE TREES & TOPOGRAPHY.  
AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B"  
BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
15

ESTABLISHED SW COR OF SE1/4 OF  
FRL. SW1/4 OF S-31 ON LINE  
BETWEEN FD. S1/4 COR AND FD SW  
COR OF S-31 AND AT PRORATED  
DISTANCE TO US GLG RUN-OUT.  
CTR OF E-W B.TOP (30.6' WIDE  
US-10) IS 1.3' NORTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
15

SET 1/2" x 5" RODD IN SMALL  
PATCH.  
7" N.PINE 805°N 57.41'  
POWER POLE 830°N 42.98'  
9" N.PINE 850°N 88.77'  
DROKVE 5/8" x 3/4" RODD WITH  
RLS CAP N00°27'E 33.00'  
SET CEDAR POST WITH  
LOC. TAB NORTH 33'

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by Carl T. Kiiskila

Date 1-19-95

Surveyor's Michigan License No. 33981