

CLIFFEY &
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0269

For corners in

APR 06 1995

COMMISSION

Lake (County)	Located In:	Corner Code #
1. Public Land Survey	T 18N R 12W	G-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN) RECORDED 14 4 DAY OF
COUNTY OF LAKE) 1894 A.D. at
O'clock 11:30 A.M.
Sumner K. Wilson REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2 - 1/4 corner common to Sections 3 and 4, T18N, R12W, Cherry Valley Township, Lake Co., Mi.

1838 - John Hodgson, G.L.O.
#1 - 10" Spruce S64°E 28 Links
#2 - 6" Cedar N47°W 28 Links

1977 - Carl Roser, L.S. 12028 (D.N.R. Sur.)
Restored corner by standard BLM instruction in area of North and South fence on ground
#3 - 11" Cedar Stump North 20.3'
#4 - 5" Cedar N85°E 8.7'
#5 - 6" Cedar S35°E 6.8'
L.C.R.C. Liber 02, Page 352.

1991 - Robert L. Wetherell, LS 24624
Survey recorded in Liber 3, Pg. 269.
Found D.N.R. monument 2714.17 feet South of N.W. corner of Sec. 3.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2 - 1/4 corner common to Sections 3 and 4, T18N, R12W, Cherry Valley Township, Lake Co., Mi.

I found D.N.R. aluminum capped pipe monument in large Cedar swamp, 300 feet more or less North of two track road. Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found remains, #4 Found down, #5 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 11/8/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2 - 1/4 corner common to Sections 3 and 4, T18N, R12W, Cherry Valley Township, Lake Co., Mi.

I accepted the D.N.R. Monument as a substantial monument, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 9" Cedar S10°E 70.15' (60d spike in W. side of tree)
- 7" Cedar S54°W 41.48' (60d spike in E. side of tree)
- 7" Cedar N20°W 40.34' (60d spike in S.W. side of tree)
- 7" Cedar S27°E 7.00' (60d spike in N.E. side of tree) Tree Scribed "1/4S." (#5)
- 8" Cedar Post Southeast 1.5'

Signed by Robert L. Wetherell

24624

Date 11/9/94

Surveyor's Michigan License No. _____

