

RECORDATION  
 APR 03 1995  
 COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**LIBER 003 PAGE 0271**

For corners in

Lake (County)	Located in:		Corner Code #
	18N	12W	
1. Public Land Survey	T	R	H-3
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

STATE OF MICHIGAN ) RECORDED 14<sup>th</sup> DAY OF  
 COUNTY OF LAKE ) NOV 19 94 A.D. at  
 O'clock 11:30 AM.  
*James A. Dechow* REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3								●					
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Robert L. Wetherell, in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-3 - 1/4 corner common to Sections 3 and 10, T18N, R12W, Cherry Valley Twp., Lake Co., Mi.
- |                                       |   |  |
|---------------------------------------|---|--|
| 1838 - John Hodgson, G.L.O.           | 1922 - George Johnson, Lake County Surveyor | 1973 - Carl Roser, LS 12028  |
| #1 - 8" W. Oak N30°W 8 Links          | Large Stone                                 | Found Large Stone from one of George Johnson's Witnesses. (Set aluminum capped D.N.R. Monument). |
| #2 - 7" B. Oak S47°W 28 Links         | #3 - 6" B. Oak N34°W 84 Links               | #5 - 6" B. Oak N30°E 56.4'   |
| #4 - 18" Y. Pine Stump S57°E 74 Links |   | #6 - 6" W. Oak N60°E 51.4'   |
|                                       |   | #7 - P. Pole S85°E 109.70'   |
- Recorded L.C.R.C. in Liber 02, Page 257, in 1975.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-3 - 1/4 corner common to Sections 3 and 10, T18N, R12W, Cherry Valley Twp., Lake Co., Mi.

I found aluminum capped D.N.R. Monument 110 feet more or less West of a North and South Power Line (Pole Line), in clear cut area. Condition of accessories is as follows: #1 gone, #2 Gone, #3 Gone, #4 Found remains of stump, #5 Found Stump, #6 Found Stump, #7 Found in good condition.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
 IN ACCORDANCE WITH S.A. 349  
 CHAIRMAN [Signature]  
 DATE 11/8/94

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-3 - 1/4 corner common to Sections 3 and 10, T18N, R12W, Cherry Valley Twp., Lake Co., Mi.

I accepted the D.N.R. Monument as a substantial monument for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

5" B. Oak N30°W 54.29' (60d spike in S.W. side of tree)  
 7" W. Oak N81°W 60.71' (60d spike in S. side of tree)  
 4" W. Oak N65°E 52.28' (60d spike in N. side of tree)  
 5" Maple S24°W 24.05' (60d spike in W. side of tree)  
 Power Pole S86°E 109.65' (Nail and Washer in N. side of pole) (#7)

Signed by Robert L. Wetherell Date 11/9/94  
 Surveyor's Michigan License No. 24624

