

JAN 25 2001

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

For corners in
Lake _____

Located in: Corner Code#

- | | | | | | |
|--------------------------------------|---|------|---|------|-----|
| 1. Public Land Survey | T | 18 N | R | 12 W | I-8 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |
| 4. Lot No. _____ Recorded Plat _____ | | | | | |
| 5. Private Claims _____ | | | | | |

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0268

DEC 8 11 17 AM '00

Shelley Myers
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on March 16, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

I-8 - 1/4 Corner common to Sections 22 & 23, T18N, R12W

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1838 - J. Hodgson, G.L.O.

- #1 - 8" Pine S19°E 10 Links
- #2 - 9" Pine N19°W 10 Links

1916 - G. H. Johnson, Co. Sur.

- 1/4" x 3' Wagon Tongue
- #3 - 5" B. Oak N77°W 62-1/2'
- #4 - 5" J. Pine S48°30'W 85'

1978 - C. Roser, LS 12028

- L.C.R.C. - Liber 02, Pg. 350
- Found 3/8" x 1-1/4" Iron
- Raised with 1/2" x 15" Pipe
- #5 - 5" W. Oak N45°W 50.3'
- #6 - 9" B. Oak S55°W 47.2'
- #7 - Cedar Post - West 33'

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1/2" x 15" pipe directly over the 1/4" x 1-1/4" Wagon Tongue. Corner is in the centerline of North and South road.


Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found in good condition, #6 Found in good condition, #7 Found down.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" pipe with a 3/4" x 24" re-bar with Lake County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 7" W. Oak N42°W 50.57' (60d spike in N.E. side) #5
- 9" W. Oak S42°W 57.58' (60d spike in N.W. side)
- 3" W. Pine S29°E 81.94' (60d spike in N.E. side)
- 4" W. Pine N42°E 78.37' (60d spike in E. side)

RATIFIED BY THE LAKE COUNTY DEED REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *RJW*
DATE *12-5-2000*



Signed by *Robert L. Wetherell*

Date December 6, 2000

Surveyor's Michigan License No. 24624