

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0418

For corners in

| Lake (County)                      | Located In:             | Corner Code =# |
|------------------------------------|-------------------------|----------------|
| 1. Public Land Survey              | T 18N R 12W             | J-9            |
|                                    | T _____ R _____         | _____          |
|                                    | T _____ R _____         | _____          |
|                                    | T _____ R _____         | _____          |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____          |
|                                    | S _____ T _____ R _____ | _____          |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____          |
|                                    | S _____ T _____ R _____ | _____          |

RECORDED  
LAKE COUNTY, MI.  
Dec 16 10 27 AM '95  
REGISTER OF DEEDS  
*Shirley M. Adams*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Robert L. Wetherell, in a field survey on November 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-9 - 1/4 Corner common to Sections 23 & 26, T18N, R12W, Lake Co., Mi.
  - 1838 - John Hodgson, G.L.O.      1978 - Robert L. Wetherell, LS 24624      1992 - Robert L. Wetherell, LS 24624
  - #1 - 7" Pine S46°E 8 Links      Found 5/8" Iron      1/2" Iron in road intersection
  - #2 - 7" Pine S40°W 11 Links      #4 - 12" B. Oak N83°E 31.47'      #7 - 17" Tw. B. Oak N25°E 58.28'
  - 1914 - George Johnson, Co. Sur.      #5 - 12" W. Pine N48°W 84.26'      #8 - 13" W. Oak N74°W 79.94'
  - Iron Kettle and Jug      #6 - 22" B. Oak S22°W 68.19'      #9 - 10" Maple S68°W 70.68'
  - #3 - 21" B. Oak N63°W 22 Links      #4 - 15" B. Oak N84°E 31.42'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 - 1/4 Corner common to Sections 23 & 26, T18N, R12W, Lake Co., Mi.

I found 1/2" re-bar with cap (could not read) in the intersection of roads North, South and West. No evidence of iron kettle or jug. there is a road cut at this location which probably destroyed corner.

Condition of the accessories are as follows: #1 Gone, #2 gone, #3 Gone, #4 Found in good condition, #5 Found stump, #6, Found in good condition, #7 Found in good condition, #8 Found stump. #9 Found in good condition.

12-12-96  
*R.L.W.*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 - 1/4 Corner common to Sections 23 & 26, T18N, R12W, Lake Co., Mi.

I replaced the 1/2" iron with a 3/4" iron with a 3/4" x 24" re-bar and Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 32" B. Oak S25°W 68.19' (60d spike in E. side) #6
- 17" Tw. B. Oak N25°E 58.28' (nail in E. side) #7
- 11" Maple S68°W 70.68' (60d spike in S.E. side) #9
- 15" B. Oak N84°E 31.42' (Nail & Cap in E. side) #4

Signed by Robert L. Wetherell

Date 12-13-1996

Surveyor's Michigan License No. 24624

