

**SURVEY & REMONUMENTATION**

DEC 1 1999

**LAND CORNER RECORDATION CERTIFICATE**

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

**SECTION**

For corners in Lake	Located in:	Corner Code#
1. Public Land Survey	T18N R13W	G-11
	T R	
	T R	
	T R	
2. Property Controlling s in Section	T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat		
5. Private Claims		

RECORDED  
LAKE COUNTY, MI.  
LIBER 004 PAGE 0230

DEC 9 9 58 AM '99

*Shelley Myers*

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Robert L. Wetherell, in a field survey on September 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

G-11 - Sec. Cor. common to Sections 27, 28, 33 & 34, T18N, R13W, Lake Co., Mi.

**A. Description of original monument and accessories and/or subsequent restoration:**

1838 - S. Sibley, G.L.O.  
#1 - 12" W. Oak S57°W 11 Links  
#2 - 6" Pine N79°E 41 Links

1914 - Lyle Shepard  
Developed plat of "Unora Park"  
This corner is S.E. cor of Plat.

1941 - G. Blass, LS 5489  
Found 1" Iron Bar  
#3 - 8" W. Oak S76°E 41.25'  
#4 - 10" W. Oak S11°E 56.40'  
#5 - 12" W. Oak N5°W 79.10'

1958 - M.S.H.D.  
Found 3/4" Iron from  
G. Blass's witnesses.  
#5 - 12" Oak N4°W 79.58'  
#3 - 11" Oak S63°E 41.42'  
#4 - 11" Oak S10°E 56.68'

1970 - L. Cavanagh, LS 17614  
Developed plat of "Arrowhead Village"  
#6 - Concrete Monument West 33.00'

1996 - R.L. Wetherell, LS 24624  
L.C.R.C. - Liber 03, Page 342  
#5 - 16" W. Oak N01°W 79.26'  
#3 - 14" W. Oak S60°E 41.47'  
#7 - 15" B. Oak S13°E 51.26'  
#8 - 7" W. Oak S53°W 36.63'

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP  
IN ACCORDANCE WITH P.A. 345  
CHAIRMAN *R. S. W.*  
DATE 10-19-99

**B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:**

I found a 4" round concrete monument 80 feet more or less West of North and South road, it checks well with the above accessories.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I accepted the 4" Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

16" W. Oak N2°W 79.26' (60d spike in W. side) #5  
14" W. Oak S60°E 41.48' (60d spike in N.E. side) #3  
16" W. Oak S13°E 51.29' (60d spike in W. side) #7  
8" W. Oak S53°W 36.63' (60d spike in N.W. side) #8

Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624

