

**SURVEY &
REMONUMENTATION**

DEC 1 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE RECORDED
FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970 LAKE COUNTY, MI.

LIBER 004 PAGE 0231
Dec 9 9 58 AM '99

Shirley Meyer
REGISTER OF DEEDS

For corners in Lake	Located in:	Corner Code#	
1. Public Land Survey	T 18N	R 13W	G-12
	T	R	
	T	R	
	T	R	
2. Property Controlling s in Section	T	R	
	S T	R	
3. Miscellaneous Property in Sec.	S T	R	
	S T	R	
4. Lot No. _____ Recorded Plat			
5. Private Claims			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on September 24, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

G-12 - 1/2 Corner common to Sections 33 & 34, T18N, R13W, Lake Co., Mi.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, G.L.O.
#1 - 8" Pine N7°E 16 Links
#2 - 6" Pine S23°W 31 Links

1953 - G. Blass, LS 5489
"Found no evidence of corner".
Set pipe midway and on line between Section corners.
#3 - 8" W. Oak N56°E 47.80'
#4 - 14" W. Oak N66°W 58.50'
#5 - 8" W. Oak S26°E 83.50'

1970 - L. Cavanagh, LS 17614
5/8" Bar
No witnesses given.
Developed plat of "Arrowhead Village".
#6 - Concrete Monument 33 feet West and 33 feet North.

CERTIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R. J. W.
DATE 10-19-99

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1/2" Pipe with 10" dock spike inside. Corner is 6 feet West of centerline of North - South road and in centerline of road to West.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" pipe with a 3/4" x 24" rebar with Lake County Remon Cap, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- 12" W. Oak N61°E 48.35' (60d spike in N.W. side) #3
- 15" W. Oak N63°W 59.11' (60d spike in S. side) #4
- 11" W. Oak S24°E 83.66' (60d spike in W. side) #5
- 8" W. Oak S34°W 90.92' (60d spike in E. side)



Signed by Robert L. Wetherell

Date 10/22/99

Surveyor's Michigan License No. 24624