

SURVEY & REMONUMENTATION

JAN 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lake (County)	Located In:		Corner Code #
	18N	14W	
1. Public Land Survey	T	R	I-3
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	
	S	T	
3. Miscellaneous Property in Sec.	S	T	
	S	T	

RECORDED
LAKE COUNTY, MI.
LIBER 004 PAGE 0091
DEC 12 11 38 AM '97
Quinn H. Dickson
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert L. Wetherell, in a field survey on October 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-3 - Section corner common to Sections 2, 3, 10 & 11, T18N, R14W, Lake Co., MI.

- | | |
|---------------------------------|--|
| <u>1838 - S. Sibley, G.L.O.</u> | <u>Undated - Charles Landon</u> |
| #1 - 10" Pine S82°W 42 Links | Unregistered surveyor from Branch, Mi. |
| #2 - 10" Pine N79°E 50 Links | Gas Pipe |
| | #3 - 10" B. Oak N22-1/2°E 116 Links |
| | #4 - Tw. B. Oak N37°W 20 Links |

- 1964 - Robert Griffin, LS 13584
L.C.R.C. - Liber 01, Pg. 124.
Found 1/2" Pipe. Replaced with a 5" Square Concrete Monument.
#5 - 6" W. Oak N52°E 154.72'
#6 - 4" R. Pine S84°E 85.82'
#7 - 5" R. Oak S43°W 108.94'
#4 - Tw. B. Oak N34°W 13.32'
#8 - 4" R. Pine N35°W 118.36'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 - Section corner common to Sections 2, 3, 10 & 11, T18N, R14W, Lake Co., MI.

I found the 5" Square Concrete Monument 25 feet South of dirt road running West and 30 feet West of dirt road running North and South.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Found in good condition, #6 Found in good condition, #7 Found in good condition, #8 Found down.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN R.L.W.
DATE 12-10-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 - Section corner common to Sections 2, 3, 10 & 11, T18N, R14W, Lake Co., MI.

I accepted the 5" Square Concrete Monument as a substantial marker for the corner, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 9" W. Oak N58°E 154.65' (dock spike in N.W. side) #5
- 9" R. Pine S84°E 85.82' (dock spike in N.E. side) #6
- 10" R. Oak S46°W 108.85' (dock spike in N.W. side) #7
- 8" R. Pine N36°W 106.72' (dock spike in N.E. side)

Signed by Robert L. Wetherell Date 12-12-97
Surveyor's Michigan License No. 24624

