

**SURVEY &
REMONUMENTATION**

DEC 9 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

For corners in Lake _____	Located in:	Corner Code #
1. Public Land Survey	T 18N R 14W	K-7
	T R	
	T R	
	T R	
2. Property Controlling s in Section	T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat		
5. Private Claims		

RECORDED
LAKE COUNTY, MI
LIBER 004 PAGE 0233

DEC 9 9 58 AM '99

Charles Myers

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on October 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree Of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

K-7 - Section corner common to Sections 13, 14, 23 & 24, T18N, R14W, Lake Co., MI.

A. Description of original monument and accessories and/or subsequent restoration:

1838 - S. Sibley, C.L.O.

#1 - 14" Pine N88°E 28 Links
#2 - 12" Pine S82°W 32 Links

1925 - G. H. Johnson, Co. Sur.

Iron Pipe
#3 - 10" B. Oak N47°W 58'
#4 - 8" B. Oak S5°W 76'

1937 - Wm. Downey - M.S.H.D.

#3 - 16" Oak N44°W 58.54'
#5 - 12" Oak S63°E 83.08'
#4 - 14" Oak South 76.32'
"Corner is 1.67' N. of centerline".

1964 - R.A. Griffin, LS 13584

L.C.R.C. - Liber 01, Pg. 134
#6 - 6" W. Oak N40°E 92.78'
#7 - 9" B. Oak S34°E 96.41'
#4 - 18" B. Oak South 76.32'
#3 - 16" B. Oak N48°W 58.22'
#8 - 5" x 7' Post North 73.33'

1983 - C. Cole, LS 17615

Survey recorded Liber 02, Page 486
Accessories same as 1964 by Griffin.

RATIFIED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *R.S.W.*
DATE 10-19-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 1" rod in monument box 1.5' feet more or less North of centerline of U.S. 10.

Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Found in good condition, #5 Gone, #6 Found in good condition, #7 Found in good condition, #8 Found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the 1" rod in monument box as a substantial marker for the corner, and is accepted as a careful and faithful reestablishment of the position of the original corner.

8" W. Oak N44°E 92.78' (Dock spike in N.W. side) #6
10" B. Oak S34°E 96.41' (Dock spike in S.W. side) #7
27" B. Oak S9°W 76.49' (60d spike in W. side) #4
7" W. Oak N12°W 68.38' (60d spike in W. side)

Signed by

Robert L. Wetherell

Date

10/22/99

Surveyor's Michigan License No. 24624

