

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 11 W.	C-12; D-12
2. PROPERTY CONTROLLING IN SECTION 32	T. 19 N. R. 11 W.	8
3. MISCELLANEOUS PROPERTY IN SECTION 32	T. 19 N. R. 11 W. & 2301.88 W of E-12)	YY (328.84 E of D-12
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on May 20, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. ~~Field survey description of corner points~~
C. (continued)

YY
Set 1/2"x3/8"x18" iron &
cedar post w/loc. tag
5" B. Oak S55°E 4.70
3" W. Pine S20°W 9.16

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-12 Reestablished 1/4 corner equidistant & on line between section corners to N & S.
 - D-12 Found 1" pipe for center of Sec. 32, per previous surveys of record by George Johnson and E. Titsworth.
 - 8 Established NE corner of NW 1/4 of SW 1/4 of Sec. 32, equidistant & on line between the center & W 1/4 of sec. 32. Note - Found 1" pipe NE of corner is 2' N of end of old fence from E.
 - YY Established the NW corner of E 3/4 of NW 1/4 of SE 1/4 of Sec. 32; on N line of SE 1/4 of Sec. 32 and 328.84', S89°27'40"E of center of Sec. 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12	D-12	8
Set DNR mon. & cedar post	Found & accepted 1" pipe	Set 1"x36" pipe & cedar post
3" W. Pine N40°W 5.6	4" B. Oak N60°W 47.9	w/loc. tag
4" W. Oak S55°E 10.1	6" W. Oak N85°E 40.3	7" W. Oak S35°E 17.4
	3" R. Pine S20°W 80.9	5" W. Oak N60°W 24.5
	Set cedar post w/loc. tag	Fd. 1" Pipe N21°27'E 35.51
	by old fn. corner	
	Due W 33'	


SIGNED BY Carl F. Roser 4-28-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ELLSWORTH TOWNSHIP
LAKE COUNTY