

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 11 W.	D-13; E-12; E-13
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	32, T. 19 N. R. 11 W.	X (822.16 W of D-13 & 1808.77 E of C-13)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 27, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on May 17, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of corner evidence found and/or method applied in restoring or re-establishing corner:~~

C. (continued)

X
Set 1/2"x3/8"x18" iron & cedar post w/loc. tag
15" B. Oak N40°W 35.48
12" J. Pine N60°E 7.48
Q E-W Trail Due S 16'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-13 Recovered two old pipes & pointed stake bottom & one witness that fits previous survey in 32 by Geo. Johnson. Also fits survey of N-S 1/4 line, Sec. 32, by E. Titsworth, 10/33.
- E-12 Reestablished 1/4 corner equidistant & on line between section corners to N & S.
- E-13 Reestablished corner common to Sec. 32 & 33 on S line of T19N-R11W, at record U.S. distance W. (60 links) of closing corner & on line between NE Sec. 5 (18-11) & S 1/4 Sec. 32 (19-11). This fits previous survey to reestablish NE Sec. 5 by Nowak & Fraus.
- X Established SE corner of W 3/8 of SE 1/4 of SW 1/4 of Sec. 32; on the S line of SW 1/4 S-32 and 822.16' N89°58'30"W of S 1/4 Sec. 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13	E-12	E-13
Fd. pipes & added DNR mon.	Set DNR mon. & cedar post	Set DNR mon. & cedar post
7" W. Pine N70°W 64.4	6" R. Oak N25°W 18.2	3" W. Oak N25°W 13.4
8" W. Oak in clp. of 3	4" R. Maple N65°E 22.9	17" W. Oak N45°E 52.2
N41°W 72.6	Fd. 1" pipe S12°E 66.19	NE corner Sec. 5 (18-11)
N 1/4 S-5 (18-11) N89°25'E 41.29	Old N-S fence Due E 96'	N89°24'40"E 39.60
Set cedar post w/loc. tag		
Due E 41'		
Fd. 3/4" pipes		
Due E & Due W 19.9'		

SIGNED BY Carl F. Roser 4-28-77 DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

ELLSWORTH TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____