

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. N. S., R. E. W.	
2. PROPERTY CONTROLLING IN SECTION 3	T. 19 N. ● R. 11 ● W. ●	8, 3, 1
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on MARCH 7, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1 (CONT) COR'S IN T20N R11W (SEE **NE** COR OF SEC 4, COR CODE G-1, T19N R11W); IT WOULD BE HIGHLY INCONSISTENT TO STAKE A SINGLE PROPORTION 1/8 COR POSITION 4.5'-W.

b. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 8 FD & ACCEPTED 1 1/4" PIPE FOR SE COR OF SW 1/4 OF FRL NW 1/4 OF SEC 3; BELIEVD TO HAVE BEEN SET BY G.H.JOHNSON (DATE UNKNOWN). A CALC 1/8 COR POSITION WOULD BE 1.4'-N & 0.9'-E.
- 3 FD OLD 1" PIPE AS SET BY G.H.JOHNSON (DATE UNKNOWN) FOR NW COR OF SW 1/4 OF FRL NW 1/4 OF SEC 3. A CALC 1/8 COR POSITION WOULD BE 5.3'-S & 0.7'-W.
- 1 FD & ACCEPTED 3/4" X 54" PIPE, IN LINE WITH FENCE TO SOUTH, FOR NW COR OF NE-NW OF SEC 3. BELIEVED TO HAVE BEEN SET BY CO. SURVEYOR, G.H.JOHNSON FROM HIS OLD SURVEY RECORDS OF SURVEY OF PART OF NW 1/4 OF SEC 3 (DATE UNKNOWN). IN VIEW OF THE FACT THAT THE NW COR OF SEC 3 & N 1/4 COR OF SEC 4 HAD TO BE ACCEPTED AS COMM COR'S TO ADJOINING

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8	3	1
FD 1 1/4" GALV PIPE; ADDED RLS CAP & CED POST W/LOC TAG.	FD OLD 1" PIPE; ADDED RLS CAP & CED POST W/LOC TAG.	FD 3/4" X 54" GALV PIPE.
5" MAPLE N70°W 19.0'	3" W PINE N70°E 3.0'	6" R PINE S10°W 57.73'
3" W PINE S75°E 33.0'	4" W PINE S15°W 19.0'	8" R PINE S50°W 84.43'
3" R OAK S25°E 29.2'	3" W PINE S65°W 10.8'	SET CED POST W/LOC TAG. DUE S 33'
		CTR E-W DIRT RD DUE S 4'
		NEWER FN COR (FN'S W & S) DUE S 31'


SIGNED BY Carl F. Roser 6-19-84 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ ELLSWORTH TWP.
LAKE COUNTY