

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N., R. 11 W.	I-7, I-6, H-7
2. PROPERTY CONTROLLING IN SECTION	15 T. 19 N., R. 11 W.	16,
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSEK, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on MARCH 13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on, 19., found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law.

C. (CONTINUED)

<p>I-6 FD 1/2" REROD W/RLS CAP AT OLD FN COR; ADDED CED POST. * 6" W PINE N65°E 29.60 * 4" W PINE S85°W 34.95 * 10" R OAK N30°W 42.51</p>	<p>H-7 SET DNR MON & CED POST. 5" W PINE N05°W 51.5 5" MAPLE N55°E 20.7 9" BEECH S25°W 7.8 EXIST. E-W 2-TRACT TRL. SOUTH 17'±</p>
---	---

* = COLE'S WITS.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-7 ACCEPTED 1/2" REROD BY RLS, CLINT COLE, FOR SW COR OF SEC 14. COR WAS PLACED ON BASIS OF DBL. DISTANCE & ON LINE ACROSS 1/8 COR & 1/4 COR TO SOUTH. AN OLD FN COR (FN'S N & E) ON GRID IS 8' (±2') W & 34' (±2') N.
- 16 FD 3/4" IR & CROCKERY, BURIED 22", IN APPROX CTR OF E-W DIRT ROAD.
- I-6 ACCEPTED 1/2" REROD AT OLD COR FN POST (FN'S N-S-W). REROD BY RLS, CLINT COLE.
- H-7 REESTAB. S 1/4 COR, SEC 15 AT DBL DISTANCE & ON LINE ACROSS FD SE COR ^{OF S-15 & FD (OLD) E-16 COR.} IRREG N-S FN REMAINS TO SOUTH ARE 22'±S. & 15'±E. OLDER E-W FN REMAINS (WIRE IN CTR OF TREES) IS 3'±S. CTR OF REAL OLD (OVER-GROWN) IRREG E-W HORSE & BUGGY TRAIL IS 5'±N. CALC S.P. POSITION WOULD BE 8'±W & 6'±N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>I-7 FD 1/2" REROD W/RLS CAP. 6" MAPLE N60°W 56.69 15" W PINE S10°E 92.43 11" R PINE S50°W 61.50 SET CED POST NORTH 33' CTR E-W GR RD NORTH 2'± CTR GR RD S'LY WEST 4'±</p>	<p>16 FD 3/4" IR & CROCKERY; RAISED W/ 5/8" X 34" REROD W/RLS CAP. 5" R OAK N10°W 37.46 3" R OAK N35°E 38.82 10" MAPLE S50°E 36.22 SET POST W/LOC TAG. DUL N 33'</p>
---	--


SIGNED BY Carl F. Rosek 6-19-84 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

ELLSWORTH TWP
LAKE COUNTY