

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 11 W.	I-5, J-5, K-5
2. PROPERTY CONTROLLED IN SECTION	15 T. 19 N. R. 11 W.	2
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. W.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on MARCH 13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

C. (CONTINUED)

~~XX~~

J-5	K-5
FD I 1/2" PIPE W/AXLE SHAFT INSIDE; ADDED CED POST W/LOC TAG, 8" R PINE S85°W 13.51 10" R PINE N60°W 23.42 32" SUG MAP N30°E 114.73	FD T-IRON (FLUSH) 12" R PINE S55°W 63.05 P POLE N60°E 62.58 26" SUG MAPLE N30°E 59.38 CTR N-S BIT RD DUE W 8' SLT CED POST W/LOC TAG. S45°W 47'


- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-5 FD 2" PIPE, 1 FT NW OF OLD COR IN POST (FN'S N-S-E-W). COR FITS 3-BLASS 1966 WITS. & POSSIBLE U.S.B.T. PINE STUMP REMAINS.
 - 2 ESTAB NE COR OF NW 1/4 OF NE 1/4 OF SEC 15 MID-WAY & ON LINE BETW THE NE COR & 1/4 COR OF SEC 15.
 - J-5 FD & ACCEPTED 1 1/2" PIPE WITH AXLE SHAFT INSIDE FOR S 1/4 COR, SEC 11; FITS 2-1981 CLINT COLE WITS AND BLOSS SEC 11 SUB'N.
 - K-5 FD T-IR (FLUSH) THAT FITS ONE 1966 BLOSS WIT. FD NAIL WITH RLS TAG #1237, WEST 7.77'. COR IS IN LINE WITH 2-TRACK WEST & APPROX CTR OF GRAVEL RD EAST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5	2
FD 2" IR PIPE & ADDED CED POST W/LOC TAG, 10" MAPLE N55°W 20.42 8" MAPLE N60°E 28.90 12" TW MAP S57°W 36.65	SET 5/8" X 3/4" REROD W/RLS CAP & CED POST W/LOC TAG, 6" SOFT MAP N50°W 6.2' 11" SOFT MAP S55°W 12.7' 6" SUG MAP S80°E 8.9' E-W FN (MOSTLY DOWN) SOUTH 28'±

SIGNED BY Carl F. Roser 6-19-84 DATE

SURVEYORS MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
ELL SWORTH TWP
LAKE COUNTY