LAND CORNER RECORDATION CERTIFICATE

	Filing Require	ement of Act /4,	Mich. PA 1970		
For Corners In:	Located In	Corner Code #	LAKE COUNTY SHELL	RECORDED 05/05/2014 3:56:18 PM LAKE COUNTY, MI Y MYERS, REGISTER OF DEEDS	
(County)			OF TEAN OF THE PARTY OF THE PAR	RECEIVED 05/05/2014 3:55:21 PM	
1. Public Land Survey	T 19N R 11W R	F2		LAKE COUNTY, MICHIGAN LY MYERS, CLERK/REGISTER/CFO RECEIPT# 5785, STATION 1	
2. Property Controlling in Section S 4	T 19N R 11W	8	\$14.00 L	ÄND CORNER	
3. Miscellaneous Property in Section	_ ' \ _ T R		88 5 1	Liber C8 Page 5	
S	_ T R		Register of D	eeds Stamp & File Number	
4. Lot No: Recorded Plat:			A B C D E F	GHIJKLM	
5. Private Claims:			2 6 5 6)—— 3——— 1——	
I, <u>Joshua R. Davidson</u> , in a field survey on <u>April 16</u> , <u>2014</u> do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below: NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.					
A. Description of original monument and accessories and/or subsequent restoration:					
F2 – Center of section 4, T19N, R11W 8 – CW 1/16 corner section 4					
Established ctr of sec 4 at intersection of ¼ lines. Set 5/8" X 34" rerod W/rls cap & cedar post. – 5" W Pine N85°W 74.3'; 8" W Pine S60°E 60.8'; 3" W Pine S10°W 65.5'. -1 ½ S6			976 – Certificate of Survey L.2, P.85 – C. Cole, PS 7615 – Survey Marker set. 982 – LCRC L. 3, P. 20 – C. Roser, PS #12028 – Fd. rerod by Clint Cole for SE cor of SW ¼ - NW ¼ of c. 4. Added CED post W/loc tag. – 5" W Pine N80°W .7'; 6" W Pine N65°E 41.2'.		
B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:					
F2 – Center of section 4, T19N, R11W		<u>8</u> – CW	8 – CW 1/16 corner section 4		
Found 5/8" rebar & broken cap #12028. Did not use this position as it is based on the rejected positions of F1 & F3. Set a stamped 2" aluminum cap on 5/8" X 34" rebar at the intersection of ¼ lines per standard BLM procedure.		F3. this ne Set	Found ½" rebar and cap with illegible number. Did not use this position as it is based on the rejected position of F2. Set a stamped 2" aluminum cap on 5/8" X 34" rebar per standard BLM procedure.		
C. Description of monument for co	rner and accessories esta	ablished to perpetu	uate locating the position of t	he corner:	
F2 – a stamped 2" Aluminum Cap on 5/8" X 34" rebar.		<u>8</u> – a st	8 – a stamped 2" Aluminum Cap on 5/8" X 34" rebar		
N12°E 26.51' to set nail & tag in E. side 5" W. Pine S48°E 42.65' to set nail & tag in SW. side 19" W. Pine S32°W 72.45' to set nail & tag in NW. side 16" W. Pine N87°47'W 21.79' to found 5/8" rebar		S3 N0	N58°E 32.24' to set nail & tag in NW. side 20" W. Pine S35°W 6.73' to set nail & tag in NW. side 6" W. Pine N08°W 26.62' to set nail & tag in S. side 11" W. Pine N87°58'W 10.73' to found ½" rebar & cap		
Set blue post with location tag 1' East. Set blue post with location tag 1' Northwest					
Signed by:	7) .,	Date	2	ing ing Na	
Surveyor's Michigan License No	.: 46659		May 5, 2014	- Stippermenter	