

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: <u>Lake</u> (County)	Located In _____	Corner Code # _____
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T 19N R 11W	12
	S <u>4</u> T 19N R 11W	13
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		



RECEIVED  
05/05/2014 3:55:21 PM  
LAKE COUNTY, MICHIGAN  
SHELLY MYERS, CLERK/REGISTER/CFO

RECORDED  
05/05/2014 3:56:18 PM  
LAKE COUNTY, MI  
SHELLY MYERS, REGISTER OF DEEDS

RECEIPT# 5785, STATION 1  
\$14.00 LAND CORNER



Liber C8

Page 7

Register of Deeds Stamp & File Number

I, Joshua R. Davidson, in a field survey on April 16, 2014 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2			1
3						●	●						
4	7		8			9		10		11			12
5													
6	18		17			16		15		14			13
7													
8	19		20			21		22		23			24
9													
10	30		29			28		27		26			25
11													
12	31		32			33		34		35			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

**12 – CS 1/16 corner section 4**

– None.

**13 – SE 1/16 corner section 4**

– None.



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**12 – CS 1/16 corner section 4**

Set a stamped 2" aluminum cap on 5/8" X 34" rebar per standard BLM procedure.

**13 – SE 1/16 corner section 4**

Set a stamped 2" aluminum cap on 5/8" X 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**12 – a stamped 2" Aluminum Cap on 5/8" X 34" rebar.**

S57°E 25.66' to set nail & tag in NE. side 3", 6" tw. R. Maple  
 S33°W 22.62' to set nail & tag in NW. side 16" W. Pine  
 S80°W 41.78' to set nail & tag in N. side 9" W. Pine  
 N20°W 45.47' to set nail & tag in W. side 4" W. Pine

Set blue post with location tag 1' Northwest

**13 – a stamped 2" Aluminum Cap on 5/8" X 34" rebar**

N36°E 39.25' to set nail & tag in NW. side 3" W. Pine  
 S88°E 7.38' to set nail & tag in N. side 3" Oak  
 S08°W 19.42' to set nail & tag in E. side 4" W. Pine  
 N32°W 12.42' to set nail & tag in SW. side 4" W. Pine

Set blue post with location tag 1' Northeast

Signed by:

*Joshua R. Davidson*

Surveyor's Michigan License No.: 46659

Date:

MAY 5, 2014