

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 003 PAGE 0232

COMMISSION:

For corners in

Lake (County)	Located In:	Corner Code --#
1. Public Land Survey	T 19 N R 11 W	J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED  
LAKE COUNTY, MI.  
OCT 7 3 46 PM '94  
REGISTER OF DEEDS  
REGISTER OF DEEDS Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on April 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

J-13 - (South 1/4 corner - Section 35, T19N, R11W)

1837 - John Hodgson, D.S., G.L.O.  
14" Hemlock for 1/4 corner

1980 - Robert L. Wetherell, LS 24624  
Set 1/2" Iron on line between Section corners  
and in line with old fence to the North.  
#1 - 3" Hemlock S20°W 37.60'  
#2 - 8" Cedar N42°W 54.26'  
#3 - 5" Gray Birch S56°E 27.96'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 - (South 1/4 corner - Section 35, T19N, R11W)

Found 1/2" iron I set in 1980, 2614.38 feet from the Southeast corner and 2607.74 feet from the Southwest corner of Section 35. Corner is in East and West fence line, in line with old fence to the North, 71 feet more or less West of small creek, (G.L.O. reported 1.5 Chains).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 - (South 1/4 corner - Section 35, T19N, R11W)

I replaced the 1/2" iron with 3/4" x 24" re-bar with Lake County Brass Cap, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- 7" Maple N18°E 74.24' (60d spike in North side of tree)
- 10" Maple N81°W 47.53' (60d spike in North side of tree)
- 9" G. Birch S55°E 27.93' (60d spike in S.W. side of tree) (#3)
- 5" Hemlock S28°W 37.50' (60d spke in West side of tree) (#1)

Signed by Robert L. Wetherell  
24624

Date October 4, 1994

