

DEC 2 9 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
LAKE COUNTY, MI.

LIBER 004 PAGE 0149  
OCT 29 4 38 PM '98

*Shirley H. Richard*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Lake

(County)	Located In:		Corner Code #
	19N	11W	M-4
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert L. Wetherell, in a field survey on June 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-4 - E.1/4 corner Section 12, T19N, R11W, Lake Co., Mi.

<u>1891 - S. Sibley, G.L.O.</u>	<u>1891 to 1904 m/l</u>
#1 - 7" Birch S50°W 20 Links	The Township of Leroy (T19N, R10W)
#2 - 10" Beech N84°W 7 Links	contracted surveyors Temple & Trumbull
	to remonument the entire Township.
	They used 3" Glazed Tiles with cinders
	for the monument.

1987 - Clinton E. Cole, LS 17615

Found 1/2" Rod in Tile  
 #3 - 14" R. Pine N57°E 64.04'  
 #4 - 16" W. Pine S38°E 73.12'  
 #5 - 6" R. Pine S63°W 81.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 - E.1/4 corner Section 12, T19N, R11W, Lake Co., Mi.

I found a 1/2" rod in 3" gazed tile at the intersection of roads West and South.

Condition of the accessories is as follows: #1 Gone, #2 Gone, #3 Found in good condition, #4 Found in poor condition, #5 Gone.

RECORDED BY THE MICHIGAN DEED REVIEW BOARD  
 R. L. W.  
 10-27-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 - E.1/4 corner Section 12, T19N, R11W, Lake Co., Mi.

I placed a 3/4" x 24" re-bar with Lake County Brass Cap inside the 3" tile, and is accepted as a careful and faithful re-establishment of the position of the original corner.

- Fence Post S77°E 26.98' (60d spike in S. side)
- 18" R. Pine N58°E 63.75' (60d spike in S. side) #3
- Power Pole S63°W 90.91' (mag. nail in S. side)
- 17" W. Pine S44°E 117.40' (60d spike in N.E. side)
- 5" Tw. Cherry N31°W 43.47' (60d spike in S.W. side)

Signed by Robert L. Wetherell  
Surveyor's Michigan License No. 24624

Date 10-29-98

