

JAN 25 2001

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, Mich. P.A. 1970

SECTION

RECORDED
LAKE COUNTY, MI
LIBER 004 PAGE 0241

MAY 5 10 25 AM '00

Robert L. Wetherell

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in Lake _____	Located in:	Corner Code#
1. Public Land Survey	T 19 N R 11 W	M-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____ Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert L. Wetherell, in a field survey on March 1, 2000, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

M-8 - East 1/4 Corner Section 24, T19N, R11W, Lake Co., Mi.

A. Description of original monument and accessories and/or subsequent restoration:

1837 - J. Hodgeson, G.L.O.
#1 - 7" Beech S60°W 11 Links
#2 7" Beech N64°W 52 Links

1917 - G.H. Johnson, Lake Co. Sur.
3 foot well point
#3 - 14" Elm S50°E (no distance given)

1954 - L. Slater, M.S.H.D.
Found 1" Pipe with bricks around
#4 - 12" Pin Cherry N45°W 35.80'
#5 - Fence post S83°E 28.20'
#3 - 37" Elm S52°E 36.24'

1891-1904 - Temple (Trumbull)
The Township of Leroy (T19N R10W)
Remonumented the entire Township with
3" Glazed tiles with cinders.

1920 F. McClung, Osceola Co. Sur.
Measured 2624' North to the Sec. Corner.

B. Description of corner evidence found and/or method applied in restoring of reestablishing corner:

I found a 1-1/2" well point with crockery and bricks around it. Below the well point I found the 3" glazed tile with cinders. The corner is in the center of a North and South road and in line with fence to the East.


Condition of the accessories are as follows: #1 Gone, #2 Gone, #3 Gone, #4 Gone, #5 Found down.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 24" rebar with Lake County Remon Cap in the center of the Clay Tile, and is accepted as a careful and faithful reestablishment of the position of the original corner.

10" W. Pine N83°E 37.43' (60d spike in N. side)
18" Cherry N07°W 133.54' (60d spike in E. side)
4" Ash N74°W 30.66' (60d spike in N. side)
9" R. Pine S37°W 66.42' (60d spike in N.W. side)

VALIDATED BY THE LAKE CO. PEER REVIEW GROUP
IN ACCORDANCE WITH P.A. 345
CHAIRMAN *R.L.W.*
DATE 4-11-2000



Signed by Robert L. Wetherell
Surveyor's Michigan License No. 24624

Date April 12, 2000