

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Lake _____ Located In _____ Corner Code # _____
 (County) _____

1. Public Land Survey	T	<u>19N</u>	R	<u>12W</u>	<u>C11</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Feb. 3, 2005 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			●										
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p><u>C11</u> – GLO – Set Post – S. Sibley – 1838 Pine 20" S49°E 23 L. Pine 20" N53°W 93 L. - CSR - 1911 – NBT W. Oak 7" S83½°W 19'3" B. Oak 6" S86½°E 22'8" - LCRC – L. 2, p. 209 – C. F. Roser – 1973 Fd. 1 ¼" x 26" pipe in N-S trail on S. slope of hill. Believed to be corner from F. Jones Survey – 1935.</p>	<p>8" B. Oak N64°E 33.6' 9" W. Oak S50°E 32.0' 11" W. Oak N88°W 43.3' Fd. Post iron East 33.5'</p>
--	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C11 – Section corner common to Sections 29, 30, 31 & 32, T19N, R12W - Fd. 1 ¼" pipe, top mangled, on S. Slope of hill. Fits three C. F. Roser witnesses. 1 ¼" pipe is accepted as best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C11 – Fd. 1 ¼" pipe
 Set Blue Carsonite Post 1' Northwest
 S88°W 43.64' to set N & T in N. side 12" W. Oak (CFR)
 N32°W 42.64' to set N & T in W. side 6" Red Maple
 N54°E 26.86' to set N & T in N. side 5" Sugar Maple
 S52°E 32.38' to set N & T in S. side 12" W. Oak (CFR)
 East 33.5' to fd. Angle iron (CFR)
 East 5'± to centerline N-S trail.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 5/11/2005