



# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 19 N. 12 W. 	D-13; E-13; F-13
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. 19 N. 12 W. 	16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5-30 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- D-13 Reestablished corner per standard B.L.M. instructions.
  - E-13 Reestablished corner per standard B.L.M. instructions.
  - F-13 Reestablished corner per standard B.L.M. instructions.
  - 16 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13	E-13	F-13
Set DNR mon & Ced Gd Post	Set DNR Mon & Ced Gd Post	Set DNR Mon & Ced.Gd.Post
14" B. Oak N25E 7.1'	10" Maple N38W 25.6	7" Cedar N80W 23.8
8" J. Pine N73W 29.4'	12" W. Pine N87E 39.9	6" Cedar N58E 57.1
N $\frac{1}{2}$ cor Sec 5 Due E 13.51	Cor of Sec 4&5 Due E 11.81	N $\frac{1}{2}$ Sec 4 Due E 10.17

Code 16  
 Set 1"x5' pipe & Ced Gd Post w/loc tag  
 10" Cedar N08E 31.6'  
 9" Cedar N49W 26.2'  
 E 1/16 on N line 4 Due E 9.95'


SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_