

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W.	K-10; K-11; L-11; M-11
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4-23 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19 , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and of subsequent corner:

C. Cont: M-11
 Set DNR Mon (buried 1 1/2')
 6" W. Pine S40W 84.2
 11" W. Pine N45W 64.4
 NW'ly leg steel
 tower #3933 S45E 51.5
 Ctr N-S Sand Rd Due E 11'±
 Set Ced. Post w/loc. tag Due W 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-10 Reestablished corner per standard B.L.M. instructions.
 K-11 Reestablished corner on straight line projection West of East 1/4 mile of South line of Sec. as occupied, old fn. and fn ridge, there being a record of survey for this mile dated 5/8/1908. Corner as reestablished fits a position by dbl. prop. reasonably close.
 L-11 Reestablished corner per std. B.L.M. instructions.
 M-11 Corner restored in line with fn. remains and ridge to West and 45' West of N-S Consumers Power high line. Fits occupancy and old survey of record by G.H. Johnson.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	K-10	K-11	L-11
Set DNR Mon & Ced. Gd Post	Set DNR Mon & Ced Gd Post	Set DNR Mon & Ced Gd Post	
7" Maple N55E 22.9	9" W. Oak S58W 34.8	20" W. Oak N73W 34.0	
4" Cedar S18E 32.8	13" W. Oak N60W 32.9	13" W. Oak S55W 64.7	
10" Hemlock S86W 36.9	7" Maple N57E 30.2	5" R. Pine in	
		Nly row of Pines S20E 67.8	

SIGNED BY Carl F. Roser DATE 7-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

