

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>19</u> ^{N.} ● , R. <u>12</u> [●] W.	<u>C-7, D-7, E-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-14-1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-7** Recovered F. Jones Iron & Witness from 1935 survey.
- D-7** Recovered F. Jones Pipe & Witness from 1935 Survey. Corner also used and witnessed by Geo. Glass.
- E-7** Recovered F. Jones Pipe & Witness from 1935 Survey. Corner also used & witnessed by Geo. Blass.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7	D-7	E-7
Fd. 1" Shaft. Added DNR Mon & Ced.Gd.Post	Fd. 1 1/2" Pipe in rd. inter. Added DNR Mon.	Fd. 1/2" pipe over 2" pipe. Added DNR Mon.
19" J. Pine S20E 71.5'	20" B. Oak N 3E 55.5'	9" B.Oak N 5E 50.7'
17" R. Pine S17W 63.0'	10" J. Pine S65E 78.6'	20" B.Oak N24E 74.3'
18" J. Pine N77W 119.1'	14" B.Oak S48W 67.7'	20" B.Oak S16E 79.9'
20" B. Oak N53E 28.7'	15" B.Oak N20W 45.3'	8" J.Pine S52W 63.4'
	Set Ced Post w/loc tag Due N 33'	Set Ced Post w/loc tag Due N 33'

SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

