

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>19</u> N. R. <u>12</u> W.		<u>C-11; c-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>31</u> , T. <u>19</u> N. R. <u>12</u> W.		<u>Code 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ S. R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 11-28 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-11 Found and accepted 1½"x26" pipe in N-S sand trail on S. slope of hill. Believed to be corner from F. Jones Survey, 1935.
- C-12 Reestablished corner per standard B.L.M. instructions.
- Code 14 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11	C-12	Code 14
Fd. 1½"x26" pipe	Set DNR Monument	Set 1"x36" Pipe
8" B. Oak N64E 33.6'	In clump of two	8" B. Oak S53W 25.5'
Fn. Post Iron Due E 33.5'	10" B. Oak N73W 29.8'	8" J. Pine S60E 35.9'
9" W. Oak S50E 32.0'	8" J. Pine N53E 44.4'	Ctr. N-S Sand rd Due E 8'
11" W. Oak N88W 43.3'	Ctr. N-S sand rd Due E 5'	Set Ced Post
	Set Ced Post	w/loc tag Due W 33'
	w/loc tag Due W 33'	


SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____