

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>19</u> N. <u>●</u> , R. <u>12</u> W. <u>●</u>	<u>A-10, C-8, C-10</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-22 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-10 Recovered & accepted Blass corner of record. Corner also recently used by E. Benkert, R.L.S. #1237
- C-8 Reestablished corner per standard B.L.M. instructions.
- C-10 Reestablished corner per standard BLM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	A-10	C-8	C-10
Fd. 3/4" pipe. Added DNR Mon. (buried 6")		Set DNR Mon & Ced. Gd. Post	Set DNR Mon. & Ced. Gd. Post
14" B. Oak	S50W 78.98'	9" J. Pine N69E 36.8'	8" J. Pine S71E 43.1'
(18" B. Oak)	S70E 25.32'	8" B. Oak N82W 9.9'	7" J. Pine S50W 10.9'
(Blass BT)		8" J. Pine N 6E 9.4'	Ctr. N-W Woods trail Due E 13'
Ctr. N-S sand rd Due E 2'			
Set Ced Post Due E 33'			


SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____