

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>19</u> N. <u>▲</u> , R. <u>12</u> W. <u>●</u>		<u>A-9, B-9, C-9</u>
2. PROPERTY CONTROLLING IN SECTION _____ , T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-25-72 19  , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19  , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-9 Recovered Fn. Post irons from Geo. Blass witness & accepted corner.
- B-9 Reestablished corner per standard B.L.M. instructions.
- C-9 Reestablished corner per standard BLM instructions, double proportion to U.S., 1 mile N-S-W and 2½ miles E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	A-9	B-9	C-9
Fd. two Fn. post irons 2' long. Added DNR mon buried		Set DNR Mon. & Ced. Gd. Post	Set DNR Mon & Ced. Gd. Post
P. Pole	N27W 41.30'	21" B. Oak N 8E 42.9'	7" J. Pine N60E 1.3'
18" B.Oak	S35E 65.86	18" B. Oak N70W 54.7'	10" B. Oak S 3E 27.2'
14" B.Oak	S55W 66.83	Sand rd. inter. S 5E 113'	10" B. Oak S71W 18.9'
Ctr. sand Rd S Due W 4'		9" J. Pine S37E 5.2'	Ctr E-W sand rd. Due S 255'
Ctr E-W sand road Due N 13'			


SIGNED BY Carl F. Roser DATE 1-11-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_