

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W.	C-1; I-1
2. PROPERTY CONTROLLING IN SECTION	4, T. 19 N. R. 12 W.	1
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on July 29, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-1 Reestablished corner per standard B.L.M. instructions.
- I-1 Found 1 1/4" pipe that fits standard corner to west.
- 1 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1	I-1	1
Set DNR monument	Found 1 1/4" pipe, added cedar post w/loc. tag	Set 1"x36" pipe & cedar post w/loc. tag
6" W. Oak S35°E 15.7	8" Oak S22°E 53.8	3" W. Pine S45°E 46.1
8" B. Oak S22°W 16.4	1/2" N-S Bit. Rd. Due W 36'	6" Oak S50°W 33.4
Cedar post w/loc. tag S70°W 3.5	Corner fence post N20°W 10.07	W-1/16 S line Sec. 33 S89°38'W 39.60
SW S-32 (20-12) S86°30'W 36.2	SE Sec. 34 West 51.48	Center E-W trail road Due S 40'


SIGNED BY Carl F. Roser DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____