

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 ^{N.} _○ , R. 12 _○ ^{W.}	G-7; H-7; I-7
2. PROPERTY CONTROLLING IN SECTION	T. 19 ^{N.} _○ , R. 12 _○ ^{W.}	1; 16
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} _○ , R. _○ ^{E.} _○ ^{W.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on June 20, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19__, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monumentation, accessories and original subsequent monumentation~~

C. (continued)

1	16
Found $\frac{1}{4}$ "x $1\frac{1}{2}$ "x29" iron	Found & accepted $\frac{1}{2}$ x $\frac{1}{2}$ square iron
7" W. Oak N50°W 35.6	3" Oak N27°E 54.7
10" W. Oak N10°W 17.4	Power Pole Due S 47.00
Center E-W gravel road	set ced. post w/loc. tag
Due S 16	Due N 33

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-7 Found pipe that fits irons, $\frac{1}{4}$ and $\frac{1}{2}$ mile east, and has been used by RLS Geo. Blass.
- H-7 Found iron that fits three witnesses by RLS Blass.
- I-7 Found nail in approximate intersection N-S blacktop rd. & E-W gravel rd. Nail fits three witnesses by RLS Blass.
- 1 Found iron in approximate line with fence to south. Fits corners $\frac{1}{4}$ mile E & W.
- 16 Recovered Robert Griffin, RLS, corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7	H-7	I-7
Found pipe, added DNR mon.	Found iron, added DNR mon.	Found nail, added $\frac{1}{2}$ " pipe
12" R. Pine N05°E 78.11	buried	8" W. Oak N61°W 98.9
16" R. Pine N42°E 120.64	20" W. Oak N05°W 20.40	9" Tw. WOak N24°W 119.6
11" W. Oak N45°W 84.4	19" B. Oak S37°E 69.58	SW corner of concrete slab
set ced. post w/loc. tag	Power Pole S45°W 50.05	N55°E 122.9
Due N 33	set ced. post w/loc. tag	
Center E-W gravel rd.	Due N 33	
Due S 18	Fence S'ly Due W 34	

SIGNED BY: Carl F. Roser 1-16-75 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY