

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W. O	F-7; F-9; G-8; G-9.
2. PROPERTY CONTROLLING IN SECTION	T. 19 N. R. 12 W. O	7
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on _____ 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and of subsequent re-establishment

C. (continued)	G-9	7
	Set DNR mon. & ced. post	Set 1 1/2"x30" pipe & ced. post w/loc. tag
	6" Cedar N65°W 8.6	9" Cedar N32°W 33.0
	5" Cedar N25°E 18.2	12" W. Pine N88°E 33.5
	13" Cedar S50°E 31.7	1/2" N-S grade Due E 13
	12" Hemlock S35°W 35.7	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- F-7 Restored corner from three witnesses by G. Blass, RLS.
- F-9 Restored corner per standard B.L.M. instructions (single proportion).
- G-8 Established corner per standard B.L.M. instructions, within approximately 2'.
Position as established lines up with old fence from center of Sec. 22 to E 1/4 of Sec. 22.
- G-9 Restored corner per standard B.L.M. instructions.
- 7 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7	F-9	G-8
Set DNR mon. buried 8"	set DNR mon. & ced. post	Set DNR mon. & ced. post
14" J. Pine N12°W 67.4	7" Cedar N45°W N37°W 34.8 35.0	6" Cedar N25°W 50.5
13" B. Oak S40°E 50.3	10" Cedar N75°E 24.5 25.2	6" Cedar N70°E 55.6
17" B. Oak S50°W 82.3	8" Cedar S22°E S17°E 20.2 21.0	1/2" N-S grade Due E 26
set ced. post w/loc. tag	Center Baldwin River	
Due N 33	Due W 120	


SIGNED BY Carl F. Roser DATE 1-16-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY