

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 ^{N.} _{0.} R. 12 _{0.} ^{W.}	E-12;G-12;H-11;I-12
2. PROPERTY CONTROLLING IN SECTION 33	T. 19 ^{N.} _{0.} R. 12 _{0.} ^{W.}	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. ^{N.} _{S.} R. ^{E.} _{W.}	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Carl F. Roser** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **November 7, 1974**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **19**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C. (continued)

	I-12	14
Set DNR mon. & ced. post		Set 1"x7" pipe & ced. post
5" R. Oak N20°W 21.2		w/location tag
6" R. Oak N27°E 16.4		6" Cedar N40°W 21.9
10" Maple S60°E 10.6		12" Maple N85°W 5.7
		6" Cedar S33°W 21.6

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-12 Restored corner per standard B.L.M. instructions (single proportion).
- G-12 Restored corner per standard B.L.M. instruction.
- H-11 Found and accepted 1/2"x1/2"x12" iron rod by RLS Robert Griffin. Corner is in line with fence to E and W.
- I-12 Restored corner per standard B.L.M. instructions.
- 14 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12	G-12	H-11
Set DNR mon. & ced. post	Set DNR mon., 6' pipe & ced. post	Found & accepted 1/2"x12" iron
14" W. Pine S15°E 58.9	13" Cedar N60°W 34.0	7" B. Oak S61°E 66.25
13" W. Pine S10°W 81.0	5" Cedar N60°E 14.1	Power Pole S48°W 52.79
20" R. Pine N20°W 73.7	6" Cedar S27°E 19.0	set cedar post w/loc. tag
		Due E 33


SIGNED BY: Carl F. Roser DATE: 1-16-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____

APPROVED AND SIGNED BY: _____ DATE: _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY