

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W. O	D-11; F-10; E-11; F-11
2. PROPERTY CONTROLLING IN SECTION 23	T. 19 N. R. 12 W. O	15
3. MISCELLANEOUS PROPERTY IN SECTION 28	T. 19 N. R. 12 W. O	XXX (660.44 E of F-11, 660.44 W of Code 16, S28)
4. LOT NO. ---, RECORDED PLAT ---		
5. PRIVATE CLAIMS ---		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Carl F. Roser** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **November 13, 1974**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **November 13, 1974**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

	F-11	XXX
Set 1"x30" pipe & cedar post w/loc. tag	Set DNR mon. & ced. post	Set 1"x6' pipe & ced. post w/loc. tag
7" Maple N50°E 7.0	11" Cedar N75°W 6.0	18" W. Pine N12°W 77.6
13" Maple S30°E 21.9	8" Cedar N37°E 15.8	13" Cedar S70°E 9.6
	11" Cedar S65°E 4.5	7" Cedar S82°W 14.2
	Baldwin Rvr. Due E 261'	
	(cse. S'ly)	

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- D-11 Recovered 3"x3" squared post from F. Jones witness (1935) & J. Nicholson wit. (1911).
 - E-10 Restored corner per standard B.L.M. instructions (single proportion).
 - E-11 Restored corner per standard B.L.M. instructions. *(Double proportion)*
 - F-11 Restored corner per standard B.L.M. instructions. *(single proportion)*
 - XXX Established SW corner of E $\frac{1}{2}$ -W $\frac{1}{2}$ -SE $\frac{1}{4}$ of Sec. 28, per standard B.L.M. instructions.
 - 15 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	D-11	E-10		E-11
Found sq'd. post remains, added	Set DNR mon. & ced. post	Set DNR mon. & Ced. post		Set DNR mon. & Ced. post
DNR mon. & ced. post	7" Cedar N20°E 27.2	8" W. Oak N15°E 2.8		8" W. Oak N15°E 2.8
14" B. Oak N29°W 55.0	8" Cedar S03°W 23.9	10" J. Pine S83°W 16.7		10" J. Pine S83°W 16.7
7" B. Oak S52°W 24.3	8" Cedar N85°W 13.7	9" W. Oak S12°E 33.1		9" W. Oak S12°E 33.1


SIGNED BY: _____ DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ CHIEF OF SURVEY PARTY DATE: _____

APPROVED AND SIGNED BY: _____ MICHIGAN REGISTERED LAND SURVEYOR DATE: _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY