

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 ^{N.} _● , R. 12 _● W.	H-10; J-11
2. PROPERTY CONTROLLING IN SECTION 29	T. 19 ^{N.} _● , R. 12 _● W.	15
3. MISCELLANEOUS PROPERTY IN SECTION 32	T. 19 ^{N.} _● , R. 12 _● W.	XX (659.23' E of C-11 & 1977.69' W of D-11)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Carl F. Roser** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram--over) were, in a field survey on **December 5, 1974**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **December 5, 1974**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restorations~~

C. (continued)

XX
Set 1"x30" pipe & cedar post
w/loc. tag
7" W. Oak N87°W 6.9
6" Maple N30°W 14.4
C N-S road Due E 97

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-10 Established center of Sec. 27 at intersection of ¼ lines. Corner falls in center of N-S blacktop road and is 38' north of fence to west.
 - J-11 Established corner per standard BLM instructions.
 - 15 Established corner per standard BLM instructions.
 - XX Set NW corner of NE-NW-NW of Sec. 32 per standard BLM instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10	J-11	15
Set railroad spike	Set DNR mon. & cedar post	Set 1"x30" pipe & cedar post
24" Maple N28°E 80.22	6" B. Oak S55°E 17.5	w/loc. tag
3" Oak S70°E 57.32	7" B. Oak S35°W 12.1	8" B. Oak N30°W 25.2
Cedar post w/loc. tag	4" B. Oak S80°W 12.5	6" W. Oak N07°E 18.3
Due W 33'		7" W. Oak N65°E 22.9

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY _____ DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR _____ DATE _____



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY