

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W.	H-8; I-8
2. PROPERTY CONTROLLING IN SECTION 22	T. 19 N. R. 12 W.	14
3. MISCELLANEOUS PROPERTY IN SECTION 22	T. 19 N. R. 12 W.	XX (1976.13 S of I-8 & 658.71 N of I-9)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Carl F. Roser** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on **December 9, 1974**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **December 9, 1974**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A description of original monument and accessories and/or subsequent restorations~~

C. (continued)

	XX
Set railroad spike in b-top road	
20" Maple N15°E	141.50
5" J. Pine S85°W	66.96
Cedar post w/loc. tag	
Due W	33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-8 Established center of Sec. 22 (in swamp) at intersection of 1/4 lines, which fits old line fence to east (out of swamp).
- I-8 Recovered C. Cole's 1/4-3/8"x3/8"x19" rod, in approximate center of N-S blacktop road and in line with fence west.
- 14 Established corner per standard B.L.M. instructions.
- XX Set NE corner of SE-SE-SE of Sec. 22 per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	H-8	I-8	14
Set 1"x6' pipe & cedar post w/loc. tag	3/8"x3/8"x19" iron rod	Set railroad spike in b-top road	
8" Ash N50°W 22.6	8" Aspen S42°E 42.58	30" Oak N62°W 75.65	
4" Maple N55°E 27.4	16" Elm N88°W 31.72	6" Cherry Due W 45.05	
7" Cedar S80°W 31.6	Center blacktop road	Loc. tag on corner fence post	
	Due W 5'	Due E 33'	


SIGNED BY: _____ DATE: _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ CHIEF OF SURVEY PARTY DATE: _____

APPROVED AND SIGNED BY: _____ MICHIGAN REGISTERED LAND SURVEYOR DATE: _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY