

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.	T. 19 N. R. 12 W.	D-9; E-8; E-9; G-10; G-11
2. PROPERTY CONTROLLING IN SECTION.	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION.	T. N. S. R. E. W.	
4. LOT NO. , RECORDED PLAT.		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Carl F. Roser** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on **November 12, 1974**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on **19.**, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent monuments~~

C. (continued)

G-10	G-11
Set DNR mon. & ced. post	Set DNR mon & Ced. post
7" Cedar N15°W 15.1	9" Maple N15°W 2.1
12" Cedar N37°E 38.9	8" Maple N62°W 10.3
E-W RR grade	9" Maple S07°W 37.9
Due S 107	corner fence post Due S 96 (fence E&N)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-9 Restored corner per standard B.L.M. instructions (single proportion).
- E-8 Restored corner per standard B.L.M. instructions.
- E-9 Restored corner per standard B.L.M. instructions.
- G-10 Restored corner per standard B.L.M. instructions.
- G-11 Restored corner per standard B.L.M. instructions (double prop.) Corner falls in N-S fence. Corner fence post to S was not established as a result of proper survey per testimony of daughter of man who built fence. No known corner when fence was constructed to keep cattle in.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9	E-8	E-9
Set DNR mon. & ced. post	Set DNR mon. & ced. post	Set DNR mon on 1"x5' pipe & ced. post
5" J. Pine N30°E 33.1	6" J. Pine S78°W 40.4	10" W. Ash N30°E 11.4
8" B. Oak S67°E 23.5	6" J. Pine N52°W 55.4	4" Cedar S50°E 92.2
8" B. Oak S70°W 12.3		21" W. Pine S67°W 138.4


SIGNED BY: Carl F. Roser DATE: 1-16-75

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY: _____ DATE: _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY: _____ DATE: _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY