

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 12 W.	C-3; D-3; E-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION 8	T. 19 N. R. 12 W.	XX = 1003.7' W of D-3
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 28, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 9, 1979, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - Description of original monument and accessories and/or subsequent restoration:

C. (continued)

XX

Drove 7/8"x12" iron pin in E-W b'top rd.	
Fd. iron in conc. SE corner Twin Creek	
Plat #2	S02°10'E 55.9
5" W. Oak	S35°E 68.5
Fd. 1/2" rerod w/RLS Cap	
	Due S 33.0
Ctr. bit. road	Due S 5.5

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-3 Fd. RR spike as previously used by RLS's Clint Cole & Geo. Blass. Corner is in line with center of road to north.
- D-3 Drove 3/4" pipe, equidistant & on line, between the SE & SW corners of Sec. 5. This fits RLS Clint Cole's subdivision of Sec. 8.
- E-3 Fd. bolt as indicated in Geo. Johnson's old survey notes. Corner is 1 ft. N of center of E-W b'top road. RLS Clint Cole has used this corner.
- XX Established NW corner of NE $\frac{1}{4}$ -NW $\frac{1}{4}$ -NE $\frac{1}{4}$ -NW $\frac{1}{4}$ of Sec. 8 per standard B.L.M. instructions. Fits RLS Clint Cole's subdivision of sec. 8

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3	D-3	E-3
Fd. RR spike in ctr. bit. rd.	Drove 3/4"x22" pipe	Fd. bolt & raised w/3/4"x12" pipe
11" J. Pine N45°W 82.82	8" B. Oak N35°W 41.0	15" W. Pine N05°W 99.25
Power Pole N60°E 61.54	9" B. Oak N50°E 46.3	14" B. Oak S10°E 42.83
19" B. Oak S50°E 57.30	Set ced. post w/loc. tag	4" W. Pine S60°W 104.28
Power Pole S35°W 57.82	Due N 33'	Ctr. rd. S Due W 35'
	Ctr. E-W bit. rd. Due S 4.6'	Set cedar post w/loc. tag
		N45°E 47'

SIGNED BY Carl F. Roser 7-9-80 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

SOUTH NEWKIRK TOWNSHIP
LAKE COUNTY